



**Traffic Volume** to be rechecked frequently, at regular intervals for the duration of the job appropriate to the conditions. If traffic changes from **Minor Traffic** to **Major Traffic** the correct plan must be selected starting from **Sheet 0**. To select the correct Traffic Management Plan for every location, **Sheet 0** must be completed first. **Do NOT assume that the correct plan can be chosen without using the sheet first.** If you do not have enough cones, signs or barriers to setup the Traffic Management as shown, contact your inspector. On every job hi-viz clothing and flashing beacons must be used. Roadworks Ahead sign to be used at any side roads where works cannot be seen from at least 50m away. Open manholes to be surrounded by barrier and Man-On-Watch. **Never leave an open manhole unattended.**

SR - 2L - KS - MT - >6 RWR  
Plan 1 - 2D Side 1  
Rev 1.1 - Nov 2015